

SITE INFORMATION PROJECT DESCRIPTION: INSTALLATION OF TELECOMMUNICATIONS TOWER WITH ANTENNAS AND ASSOCIATED EQUIPMENT. BURCHS CREEK RD SITE ADDRESS: BATESVILLE, VA 22924 LATITUDE (NAD 83): 37° 59' 58.4690" LONGITUDE (NAD 83): -78° 43' 09.3431" **GROUND ELEVATION** 732.5' (A.M.S.L.) JURISDICTION: ALBEMARLE COUNTY ZONING: **RA - RURAL AREAS** PARCEL ID: 07200-00-00-03200 PARCEL AREA: 1,046.98 ACRES TOTAL AREA OF DISTURBANCE: 4,440 SQ. FT. PARCEL OWNER: MILLER SCHOOL OF ALBERMARLE 1000 SAMUEL MILLER LOOP CHARLOTTESVILLE, VA 22903 TOWER OWNER: **VERIZON WIRELESS** 1831 RADY COURT RICHMOND, VA 23335 STRUCTURE TYPE: MONOPOLE **OVERALL TOWER HEIGHT:** 89.5' HEIGHT OF STRUCTURE: 87.5' RAD CENTER: 83.5' 2,500 SQ. FT. TOTAL LEASE AREA: DOMINION VIRGINIA POWER (888) 837-4966 POWER PROVIDER: **TELCO PROVIDER:** VERIZON (800) 483-3000


EMERGENCY INFORMATION:

ALBERMARLE COUNTY FIRE & RESCUE:

(434) 977-9041

ALBERMARLE COUNTY SHERIFF'S OFFICE: (434) 977-9041

PROJECT TEAM		
CONSTRUCTION MANAGER:	TCM MIKE REYNOLDS (434) 841-0752	
PROJECT MANAGEMENT FIRM:	GDN NATHAN HOLLAND (757) 8420	
ENGINEERING FIRM:	NB+C ENGINEERING SERVICES, LLC. 120 EASTSHORE DRIVE SUITE 300 GLEN ALLEN, VA 23059 (804) 548-4079	



W EXIT TOWARD CHARLOTTESVILLE. MERGE ONTO I-64. TAKE EXIT 167 FOR VA-617 TOWARD OILVILLE/GOOCHLAND. TURN RIGHT ONTO STATE RTE 617/OILVILLE RD. TURN LEFT ONTO STATE RTE 702/PONY FARM RD. TURN LEFT AT THE ACCESS ROAD LABELED 1975 PONY FARM ROAD. AFTER APPROXIMATELY 0.5 MILES THERE WILL BE A T INTERSECTION. CONTINUE STRAIGHT ON THE ACCESS ROAD (DO NOT TURN RIGHT AT THE INTERSECTION). CONTINUE APPROXIMATELY 0.65 MILES ALONG THE ACCESS ROAD TO THE SITE.

 2015 INTERNATIONAL BUILDING CODE 2014 NATIONAL ELECTRICAL CODE • 2015 NFPA 101, LIFE SAFETY CODE 2015 IFC

AMERICAN CONCRETE INSTITUTE

SITE NAME: BATESVILLE

BURCHS CREEK RD BATESVILLE, VA 22924 ALBEMARLE COUNTY

CODE COMPLIANCE


ALL WORK AND MATERIALS SHALL BE PERFORMED AND INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THE LATEST EDITIONS OF THE FOLLOWING CODES.


- AMERICAN INSTITUTE OF STEEL CONSTRUCTION
- MANUAL OF STEEL CONSTRUCTION 14TH EDITION
 ANSI/T 311
- 2015 VIRGINIA CONSTRUCTION CODE
- ANSI/TIA-222-G
- TIA 607
- INSTITUTE FOR ELECTRICAL & ELECTRONICS ENGINEER 81
- IEEE C2 NATIONAL ELECTRIC SAFETY CODE LATEST EDITION
- TELECORDIA GR-1275

	DR
T-1	TITLE SHEET
EE-1	EASEMENT EXH
EE-2	EASEMENT EXH
EE-3	EASEMENT EXH
Z-1	SITE PLAN
Z-2	ADJACENT PRO
Z-3	TREE INVENTO
Z-4	ENLARGED SIT
Z-5	TOPOGRAPHIC
C-1	COMPOUND PL
C-2	TOWER ELEVA
C-3	MOUNT DETAIL
S-1	CONSTRUCTIO
S-2	EQUIPMENT MO
ES-1	EROSION & SEI
ES-2	EROSION & SEI
ES-3	EROSION & SEI


TO PREVENT STORM WATER POLLUTION DURING CONSTRUCTION.

APP






Know what's **below. Call** before you dig.



ADJACENT PROPERTIES

1		RA
2		RA
3		RA
4	OWNER: ADDRESS: APN: ZONING: AREA:	85–27A RA
5		RA
6		KRAG, JAMES L OR LINDA B 1618 MILLER SCHOOL ROAD 60B RA 2.68
7		RA
8	PATTER	RA
9		RA
10		RA
11	OWNER: RAY II ADDRESS: APN: 86–0 ZONING: AREA:	N/A D2 RA
12	OWNER: ADDRESS: APN: ZONING: AREA:	86–04F RA
13		
14		
15	OWNER: MORAL ADDRESS: APN: ZONING: AREA:	N/A 86–17 RA
16	ADDRESS:	86–17A RA
17	OWNER: ADDRESS: APN: ZONING: AREA:	N/A 86–20 RA
18		H & S PROPERTIES LLC 976 POUNDING CREEK ROAD 72–32A RA 184.2
19		CLARK, STEVEN E. 5511 DICK WOODS ROAD 72–33 RA 3.24
20	ADDRESS: APN: ZONING:	H & S PROPERTIES, LLC 5390 DICK WOODS ROAD 72–54 RA 265.75
21	OWNER: ADDRESS: APN: ZONING: AREA:	

	22	CLARENCE ADDRESS: APN: ZONING:	CLAYTON, CLARENCE W. JR. & BETTY J., TRS; & BETTY CLAYTON REV LIV TR. 5656 DICK WOODS ROAD 72-34 RA 6.02
	23	ADDRESS: APN: ZONING:	FARINA, LOUIS D. OR CAROLYN D. 5758 LAYLA LANE 72–27A1 RA 16.13
	24	ADDRESS:	72–27 RA
	25	ADDRESS: APN: ZONING:	72–31
	26	ADDRESS: APN: ZONING:	72–29
	27	ADDRESS: APN: ZONING:	CROZET SPORTMANS CLUB 894 MILLER SCHOOL ROAD 72–10A RA 58.43
	28	APN: ZONING:	1111 MILLER SCHOOL ROAD 71-49
	29	ADDRESS: APN: ZONING:	DOLLINS, ROBERT ANDREW 5944 DICK WOODS ROAD 71–53 RA 11.78
	30	ADDRESS: APN: ZONING:	71–50
	31	ADDRESS: APN: ZONING:	BALLARD, DANIEL M. OR MARGARET H. 1075 BURCHS CREEK ROAD 71–54 RA 12.23
	32	ADDRESS: APN: ZONING:	KUIKEN, CHRISTINE AUSTIN 1079 BURCHS CREEK ROAD 71–56 RA 32.30
	33	ADDRESS: APN: ZONING:	71–58
	34		DOIG, POLLY DAVIS 1429 BURCHS CREEK ROAD 71–60 RA 3.24
	35	SUSANNA ADDRESS: APN: ZONING:	BROWN, W. L. LYONS III, LIFE ESTATE & S. BROWN, TRUSTEE 1500 BURCHS CREEK ROAD 71–26B1 RA 70.66
М	36	OWNER: ADDRESS: APN: ZONING: AREA:	72–32E
	37	OWNER: ADDRESS: APN: ZONING: AREA:	72–32D



Know what's **below.** Call before you dig.

TREE INVENTORY				
NUMBER	SPECIES	CALIPER	AGL HEIGHT	CANOPY HEIGHT
(84)	PINE	12"	77'	805' AMSL
(85)	PINE	12"	72'	801'AMSL
(86)	PINE	14"	71'	801' AMSL
(87)	PINE	12"	73'	804' AMSL
(88)	PINE	10"	71'	803' AMSL
(89)	PINE	12"	75'	803' AMSL
(90)	PINE	12"	73'	803' AMSL
(91)	PINE	12"	73'	806' AMSL
(92)	PINE	10"	70'	803' AMSL
(93)	PINE	10"	66'	805' AMSL
(94)	PINE	10"	63'	798' AMSL
(95)	PINE	12"	75'	810' AMSL
(96)	PINE	12"	72'	807'AMSL
(98)	PINE	10"	73'	808'AMSL
(99)	PINE	10"	72'	805' AMSL
(100)	PINE	10"	71'	804'AMSL
(101)	PINE	10"	71'	804'AMSL
(102)	PINE	10"	73'	804'AMSL
(103)	DEAD PIN			
(104)	PINE	14"	77'	805' AMSL
(105)	PINE	12"	78'	805' AMSL
(106)	PINE	14"	69'	801'AMSL
(108)	PINE	10"	66'	801'AMSL

728

\$131.0

*TOTAL TREES TO BE REMOVED: 7 NOTES:

1. REFERENCE TREE IS IDENTIFIED ABOVE IN BOLD.

TREE DRIPLINES ARE DRAWN TO SCALE.
 UNDERLINED TREE HEIGHTS HAVE BEEN

CONFIRMED BY A THIRD PARTY TOWER CLIMB.

TREES	TO BE	REMOVED

			2 · · · · · · · · · · · · · · · · · · ·	
NUMBER	SPECIES	CALIPER	AGL HEIGHT	CANOPY HEIGHT
(86)	PINE	14"	66'	796'AMSL
(87)	PINE	12"	69'	800' AMSL
(88)	PINE	10"	66'	798'AMSL
(90)	PINE	12"	69'	799' AMSL
(91)	PINE	12"	68'	801'AMSL
(94)	PINE	8"	61'	796'AMSL
(96)	PINE	12"	65'	800' AMSL

EXISTING UTILITY POLE (POLE ID: AFB43-18)

BURCHS


CREEK

B

ROND





A





LEGEND

	PROPERTY LINE – SUBJECT PARCEL
	PROPERTY LINE – ABUTTERS
	EXISTING ROAD
	EXISTING FENCE
	PROPOSED EASEMENT
	PROPOSED LEASE AREA
	EXISTING EASEMENT
	PROPOSED FENCE
OHW	EXISTING OVERHEAD UTILITY LINES
	EXISTING BUILDING






















GENERAL NOTES

1. THE CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE CODES ORDINANCES, LAWS AND REGULATIONS OF ALL MUNICIPALITIES, UTILITIES COMPANY OR OTHER PUBLIC AUTHORITIES.

2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL PERMITS AND INSPECTIONS THAT MAY BE REQUIRED BY ANY FEDERAL, STATE, COUNTY OR MUNICIPAL AUTHORITIES.

3. THE CONTRACTOR SHALL NOTIFY THE CONSTRUCTION MANAGER, IN WRITING, OF ANY CONFLICTS, ERRORS OR OMISSIONS PRIOR TO THE SUBMISSION OF BIDS OR PERFORMANCE OF WORK. MINOR OMISSIONS OR ERRORS IN THE BID DOCUMENTS SHALL NOT RELIEVE THE CONTRACTOR FROM RESPONSIBILITY FOR THE OVERALL INTENT OF THESE DRAWINGS.

4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING ALL EXISTING SITE IMPROVEMENTS PRIOR TO COMMENCING CONSTRUCTION. THE CONTRACTOR SHALL REPAIR ANY DAMAGE CAUSED AS A RESULT OF CONSTRUCTION OF THIS FACILITY.

5. THE SCOPE OF WORK FOR THIS PROJECT SHALL INCLUDE PROVIDING ALL MATERIALS, EQUIPMENT AND LABOR REQUIRED TO COMPLETE THIS PROJECT. ALL EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

6. THE CONTRACTOR SHALL VISIT THE PROJECT SITE PRIOR TO SUBMITTING A BID TO VERIFY THAT THE PROJECT CAN BE CONSTRUCTED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.

7. CONTRACTOR SHALL VERIFY ANTENNA ELEVATION AND AZIMUTH WITH RF ENGINEERING PRIOR TO INSTALLATION.

8. TRANSMITTER EQUIPMENT AND ANTENNAS ARE DESIGNED TO MEET ANSI/TIA 222-G REQUIREMENTS.

9. ALL STRUCTURAL ELEMENTS SHALL BE HOT DIPPED GALVANIZED STEEL.

10. CONTRACTOR SHALL MAKE A UTILITY "ONE CALL" TO LOCATE ALL UTILITIES PRIOR TO EXCAVATING.

11. IF ANY UNDERGROUND UTILITIES OR STRUCTURES EXIST BENEATH THE PROJECT AREA, CONTRACTOR MUST LOCATE IT AND CONTACT THE APPLICANT & THE OWNER'S REPRESENTATIVE.

12. OCCUPANCY IS LIMITED TO PERIODIC MAINTENANCE AND INSPECTION BY TECHNICIANS APPROXIMATELY 2 TIMES PER MONTH.

13. PRIOR TO THE INSTALLATION OF THE PROPOSED EQUIPMENT OR MODIFICATION OF THE EXISTING STRUCTURE, A STRUCTURAL ANALYSIS SHALL BE PERFORMED BY THE OWNER'S AGENT TO CERTIFY THAT THE EXISTING/PROPOSED COMMUNICATION STRUCTURE AND COMPONENTS ARE STRUCTURALLY ADEQUATE TO SUPPORT ALL EXISTING AND PROPOSED ANTENNAS, COAXIAL CABLES AND OTHER APPURTENANCES.

14. PROPERTY LINE INFORMATION WAS PREPARED USING DEEDS, TAX MAPS, AND PLANS OF RECORD AND SHOULD NOT BE CONSTRUED AS AN ACCURATE BOUNDARY SURVEY.

15. THIS PLAN IS SUBJECT TO ALL EASEMENTS AND RESTRICTIONS OF RECORD.

16. THE PROPOSED FACILITY WILL CAUSE ONLY A "DE MINIMIS" INCREASE IN STORMWATER RUNOFF. THEREFORE, NO DRAINAGE STRUCTURES ARE PROPOSED.

17. NO SIGNIFICANT NOISE, SMOKE, DUST, OR ODOR WILL RESULT FROM THIS FACILITY.

18. THE FACILITY IS UNMANNED AND NOT INTENDED FOR HUMAN HABITATION (NO HANDICAP ACCESS REQUIRED).


19. THE FACILITY IS UNMANNED AND DOES NOT REQUIRE POTABLE WATER OR SANITARY SERVICE.


20. POWER TO THE FACILITY WILL BE MONITORED BY A SEPARATE METER.


PROPOSED


(TYP.)

C-3









































VERIZON WIRELESS EQUIPMENT:


- CHARLES INDUSTRIES CUBE-PM63915TN2 BATTERY CABINET - CHARLES INDUSTRIES CUBE-BB48E1HN1 BATTERY CABINET - (2) RAYCAP OVP

CONTRACTOR PROVIDED EQUIPMENT:

- * THIS IS NOT A COMPREHENSIVE LIST. IT SHOULD BE ASSUMED BY THE CONTRACTOR THAT ALL OTHER ITEMS DETAILED IN THIS SET OF DRAWINGS SHALL BE PROVIDED BY THE CONTRACTOR.
- 36" WIDE X 36" TALL X 12" DEEP TELCO BOX, NEMA 3R, CABINET ENCLOSURE WITH CENTER DIVIDE, PAINTED GREY WITH WOODEN BACKBOARD, PADLOCK LATCH, AND COMBINATION LOCK.
- <u>"MISC SIDE":</u> CONTRACTOR SHALL PROVIDE (2) FILE FOLDER HOLDERS, FOLD DOWN LAPTOP DESK, AND OUTDOOR RATED COVERED GFCI FOUR PLUG RECEPTACLE. <u>"FM SIDE":</u> FIBER MANAGEMENT SPACE.
- 32" WIDE X 59" TALL X 12" DEEP, ASCO D300L SERIES POWER TRANSFER LOAD CENTER MODEL AA300G-1PH-N-3R -

- COORDINATE ADDITIONAL ENTRY GATE LOCK(S) WITH





	PROPERTY LINE - SUBJECT PARCEL
XXX	EXISTING CONTOUR LINE
	PROPOSED CONTOUR LINE
	PROPOSED FENCE
	PROPOSED LEASE AREA
	PROPOSED LIMITS OF DISTURBANCE
(SF)	PROPOSED SILT FENCE
	PROPOSED TREE PROTECTION
CE	PROPOSED CONSTRUCTION ENTRANCE

EROSION AND SEDIMENT CONTROL NARRATIVE

PROJECT DESCRIPTION THE PURPOSE OF THIS PROJECT IS THE CONSTRUCTION OF MONOPOLE TOWER, AND FENCED COMPOUND, ALONG WITH ASSOCIATED UTILITIES. THE LEASE AREA OF THE TOWER IS 2,500 SQ.FT.; THE COMPOUND AREA IS 442 SQ.FT.; THE TOTAL DISTURBED AREA IS 4,440 SF.

EXISTING SITE CONDITIONS

THE EXISTING SITE CONDITIONS CONSIST OF DENSE WOODS, SPARSE WOODLANDS AND OPEN SPACE IN GOOD AND POOR CONDITION WITH AN AVERAGE SLOPE OF 5% TO THE SOUTH EAST.

THE ADJACENT AREAS ARE UNDEVELOPED WOODLANDS AND SINGLE FAMILY RESIDENTIAL HOMES.

OFF-SITE AREAS THERE ARE NO PROPOSED OFF-SITE AREAS ASSOCIATED WITH THIS PROJECT

(27C) ELIOAK LOAM - 7 TO 15 PERCENT SLOPES (86B) TURBEVILLE LOAM - 2 TO 7 PERCENT SLOPES

<u>CRITICAL AREAS</u> THERE ARE NO CRITICAL AREAS ASSOCIATED WITH THIS PROJECT.

ESC MEASURES - STRUCTURAL PRACTICES STRUCTURAL MEASURES TO BE USED ON THE SITE INCLUDE SILT FENCE (VE&SCH SPEC. 3.05), CONSTRUCTION ENTRANCE (VE&SCH SPEC. 3.02), TREE PROTECTION FENCE (VE&SCH SPEC. 3.38), TEMPORARY STOCK PILE (VE&SCH SPEC. 3.30), AND CONCRETE WASHOUT. ALL MEASURES SELECTED ARE STANDARD ESC ITEMS FOR THIS APPLICATION. ANY DISTURBED AREA DENUDED FOR SEVEN DAYS THAT IS NOT IN ACTIVE WORK AREA TO BE TEMPORARILY SEEDED.

ESC MEASURES - VEGETATIVE PRACTICES VEGETATION PRACTICES INCLUDE TEMPORARY AND PERMANENT SEEDING (VE&SCH SPEC. 3.31 & 3.32).

PERMANENT STABILIZATION

- . UNTIL AN ADEQUATE ROOT SYSTEM IS ESTABLISHED AND IN THE ABSENCE OF ADEQUATE RAINFALL, SODDING (OR WHATEVER VEGETATION IS USED) SHALL BE IRRIGATED AS OFTEN AS NECESSARY TO MAINTAIN MOIST SOIL TO A DEPTH OF 4 INCHES. IN GENERAL, WATERING SHALL BE PERFORMED IN ACCORDANCE WITH THE VESCH.
- 2. ALL AREAS DISTURBED BY CONSTRUCTION SHALL BE STABILIZED WITH PERMANENT SEEDING IMMEDIATELY FOLLOWING FINISHED GRADING. SEEDING SHALL BE DONE WITH KENTUCKY 31 TALL FESCUE ACCORDING TO STD. AND SPEC. 3.32, PERMANENT SEEDING, OF THE HANDBOOK. EROSION CONTROL BLANKETS WILL BE INSTALLED OVER FILL SLOPES WHICH HAVE BEEN BROUGHT TO FINAL GRADE AND HAVE BEEN SEEDED TO PROTECT THE SLOPES PROPERLY. MULCH (STRAW OR FIBER) WILL BE USED ON RELATIVELY FLAT AREAS. IN ALL SEEDING OPERATIONS, SEED FERTILIZER AND LIME WILL BE APPLIED PRIOR TO MULCHING. IN ACCORDANCE WITH MINIMUM STANDARD #3, PERMANENT VEGETATION SHALL NOT BE CONSIDERED ESTABLISHED UNTIL A GROUND COVER IS ACHIEVED THAT IS UNIFORM, MATURE ENOUGH TO SURVIVE AND WILL INHIBIT EROSION.
- 3. THE LOCAL VESCP AUTHORITY REPRESENTATIVE SHALL MAKE THE DETERMINATION AS TO WEATHER OR NOT PERMANENT VEGETATION HAS BEEN ESTABLISHED IN ACCORDANCE WITH MINIMUM STANDARD #3.

UNDERGROUND UTILITY LINE INSTALLATION: UNDERGROUND UTILITY LINES SHALL BE INSTALLED IN ACCORDANCE WITH THE FOLLOWING STANDARDS IN ADDITION TO OTHER APPLICABLE CRITERIA:

- 1. NO MORE THAN 500 LINEAR FEET OF TRENCH MAY BE OPENED AT ONE TIME.
- 2. EXCAVATED MATERIAL SHALL BE PLACED ON THE UPHILL SIDE OF TRENCHES. 3. EFFLUENT FROM DEWATERING OPERATIONS SHALL BE FILTERED OR PASSED THROUGH AN APPROVED SEDIMENT
- TRAPPING DEVICE, OR BOTH, AND DISCHARGED IN A MANNER THAT DOES NOT ADVERSELY AFFECT FLOWING STREAMS OR OFF-SITE PROPERTY. 4. MATERIAL USED FOR BACKFILLING TRENCHES SHALL BE PROPERLY COMPACTED IN ORDER TO MINIMIZE EROSION
- AND PROMOTE STABILIZATION. 5. DESTABILIZATION SHALL BE ACCOMPLISHED IN ACCORDANCE WITH THESE REGULATIONS.
- 6. COMPLY WITH APPLICABLE SAFETY REGULATIONS.

CONSTRUCTION SEQUENCE

AT LEAST 7 DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES. THE O/RP SHALL INVITE ALL CONTRACTORS INVOLVED IN THOSE ACTIVITIES, THE LANDOWNER, ALL APPROPRIATE MUNICIPAL OFFICIALS, THE EROSION AND SEDIMENT CONTROL PLAN PREPARER, AND THE LOCAL VESCP AUTHORITY TO AN ON-SITE MEETING. ALSO, AT LEAST 3 WORKING DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES, ALL VIRGINIA CONTRACTORS INVOLVED IN THOSE ACTIVITIES SHALL NOTIFY THE VIRGINIA ONE CALL SYSTEM "MISS UTILITY" INCORPORATED AT 811 FOR BURIED UTILITIES LOCATIONS.

EROSION AND SEDIMENT BMPS MUST BE CONSTRUCTED. STABILIZED. AND FUNCTIONAL BEFORE SITE DISTURBANCE BEGINS WITHIN THE TRIBUTARY AREAS OF THOSE BMPS.

ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE FOLLOWING SEQUENCE. EACH STAGE SHALL BE COMPLETED BEFORE ANY FOLLOWING STAGE IS INITIATED. CLEARING AND GRUBBING SHALL BE LIMITED ONLY TO THOSE AREAS DESCRIBED IN EACH STAGE.

1. MOBILIZATION

- 2. INSTALL SILT FENCE AROUND COMPOUND AREA.
- 3. COMMENCE CLEARING AND GRUBBING. SOIL STOCKPILE AREA AND ROUGH GRADE SITE.
- 4. EXCAVATE AND POUR TOWER FOUNDATION. BACKFILL AND COMPACT FOUNDATION AREA.
- 5. CONSTRUCT AND MAINTAIN TEMPORARY COVER TO STABILIZE DISTURBED AREAS
- 6. INSTALL UTILITIES.
- 7. COLLECT SILT AND SEDIMENT AND PLACE BACK ON SITE
- 8. ESTABLISH PERMANENT COVER

9. UPON APPROVAL OF THE LOCAL VESCP AUTHORITY, REMOVE EROSION AND CONTROL MEASURES

IMMEDIATELY AFTER EARTH DISTURBANCE ACTIVITIES CEASE. THE O/RP SHALL STABILIZE ANY AREAS DISTURBED BY THE ACTIVITIES. DURING NON-GERMINATING PERIODS. MULCH MUST BE APPLIED AT THE SPECIFIED RATES. DISTURBED AREAS WHICH ARE NOT AT FINISHED GRADE AND WHICH WILL BE REDISTURBED WITHIN 1 YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE TEMPORARY VEGETATIVE STABILIZATION SPECIFICATIONS. DISTURBED AREAS WHICH ARE AT FINISHED GRADE OR WHICH WILL NOT BE REDISTURBED WITHIN 1 YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE PERMANENT VEGETATIVE STABILIZATION SPECIFICATIONS.

AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT IS UNIFORM. MATURE ENOUGH TO SURVIVE AND WILL INHIBIT EROSION. THE LOCAL VESCP AUTHORITY REPRESENTATIVE SHALL MAKE THE DETERMINATION AS TO WHEN FINAL STABILIZATION HAS BEEN ACHIEVED.

AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED. TEMPORARY EROSION AND SEDIMENT BMPS MUST BE REMOVED. AREAS DISTURBED DURING REMOVAL OF THE BMPS MUST BE STABILIZED IMMEDIATELY.

GENERAL EROSION & SEDIMENT CONTROL NOTES

- EROSION & SEDIMENT CONTROL REGULATIONS.
- IN CLEARING.
- ON THE SITE AT ALL TIMES.
- PLAN APPROVING AUTHORITY.
- AUTHORITY.

- POSSIBLE.
- HANDBOOK 3.31-B FOR SEEDING SPECIFICATION.

MAINTENANCE

- REPLACED.
- TOP OF THE BARRIER.
- AREAS SHOULD BE FERTILIZED AND RESEEDED AS NEEDED.

1. UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CONSTRUCTED AND MAINTAINED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS OF THE VA EROSION & SEDIMENT CONTROL HANDBOOK LATEST EDITION AND VIRGINIA

2. THE LOCAL PLAN APPROVING AUTHORITY (ALBEMARLE COUNTY ESC OFFICE) MUST BE NOTIFIED ONE WEEK PRIOR TO THE PRE-CONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITY AND ONE WEEK PRIOR TO THE FINAL INSPECTION. IF NO PRE-CONSTRUCTION CONFERENCE HAS OR WILL BE SCHEDULED, ONE MUST BE SCHEDULED WITH THE ALBEMARLE COUNTY ESC OFFICE. ALBEMARLE COUNTY'S ESC OFFICE TELEPHONE NUMBER IS (434) 296-5832. 3. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP

4. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN AND PERMIT SHALL BE MAINTAINED

5. PRIOR TO COMMENCING LAND DISTURBING ACTIVITIES IN AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING, BUT NOT LIMITED TO, OFF-SITE BORROW OR WASTE AREAS) THE CONTRACTOR SHALL SUBMIT A SUPPLEMENTARY EROSION CONTROL PLAN TO THE OWNER FOR REVIEW AND APPROVAL BY THE

6. THE JOB SUPERINTENDENT IS RESPONSIBLE FOR INSTALLATION OF ANY ADDED EROSION CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE LOCAL E&S

7. ALL DISTURBED AREAS ARE TO DRAIN TO APPROVED SEDIMENT CONTROL MEASURES AT ALL TIMES DURING LAND DISTURBING ACTIVITIES AND DURING SITE DEVELOPMENT UNTIL FINAL STABILIZATION IS ACHIEVED. 8. DURING DEWATERING OPERATIONS, WALL WILL BE PUMPED INTO AN APPROVED FILTERING DEVICE. 9. THE JOB SUPERINTENDENT SHALL INSPECT ALL EROSION CONTROL MEASURES DAILY AND AFTER EACH RUNOFF-PRODUCING RAINFALL EVENT. ANY NECESSARY REPAIRS OR CLEANUP TO MAINTAIN THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES SHALL BE MADE IMMEDIATELY.

MANAGEMENT STRATEGIES

1. CONSTRUCTION WILL BE SEQUENCED SO THAT GRADING OPERATIONS CAN BEGIN AND END AS QUICKLY AS

2. SEDIMENT TRAPPING MEASURES WILL BE INSTALLED AS A FIRST STEP IN GRADING AND WILL BE SEEDED AND MULCHED IMMEDIATELY FOLLOWING INSTALLATION. 3. TEMPORARY SEEDING OR OTHER STABILIZATION WILL FOLLOW IMMEDIATELY AFTER GRADING. SEE VA E&SC

4. AREAS WHICH ARE NOT TO BE DISTURBED WILL BE CLEARLY MARKED BY FLAGS, SIGNS, ETC. 5. THE JOB SUPERINTENDENT SHALL BE RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ALL EROSION AND SEDIMENT CONTROL PRACTICES. 6. AFTER ACHIEVING ADEQUATE STABILIZATION THE TEMPORARY ESC MEASURES WILL BE CLEANED UP FROM ACCUMULATED SEDIMENT AND REMOVED, ONLY AFTER APPROVAL OF THE JURISDICTION ESC INSPECTOR.

IN GENERAL, ALL EROSION AND SEDIMENT CONTROL MEASURES WILL BE CHECKED DAILY AND AFTER EACH SIGNIFICANT RAINFALL EVENT. THE FOLLOWING ITEMS WILL BE CHECKED IN PARTICULAR:

1. THE GRAVEL OUTLETS WILL BE CHECKED REGULARLY FOR SEDIMENT BUILDUP WHICH WILL PREVENT DRAINAGE. IF THE GRAVEL IS CLOGGED BY SEDIMENT, IT SHALL BE REMOVED AND CLEANED OR 2. THE SILT FENCE WILL BE CHECKED REGULARLY FOR UNDERMINING OR DETERIORATION OF THE FABRIC.

SEDIMENT SHALL BE REMOVED WHEN THE LEVEL OF SEDIMENT DEPOSITION REACHES HALFWAY TO THE 3. THE SEEDED AREAS WILL BE CHECKED REGULARLY TO ENSURE THAT A GOOD STAND IS MAINTAINED.

TOPSOIL SPECIFICATIONS

- TOOLS EQUIPMENT, SUPPLIES, AND SERVICES; AND, SHALL PERFORM ALL WORK NECESSARY FOR PROVIDING (TYPE B AS NECESSARY) AND APPLYING TOPSOIL IN ACCORDANCE WITH THE REQUIREMENTS. OF THESE SPECIFICATIONS AND IN CONFORMITY TO THE DEPTHS AND LIMITS SHOWN ON THE DRAWINGS OR AS ESTABLISHED BY THE OWNER.
- B. PRIOR TO USE OR PLACEMENT, THE CONTRACTOR SHALL SUBMIT CERTIFICATIONS OF SOIL TESTS FOR APPROVAL, SOIL TESTS SHALL BE PROVIDED AT THE RATE OF ONE TEST PER 10,000 SQUARE FEET OF DISTURBED AREA.
- C. UNLESS OTHERWISE DIRECTED BY THE OWNER, AREAS DESIGNATED TO RECEIVE TOPSOIL SHALL BE GRADED, SHAPED, AND THEN SCARIFIED OR TILLED BY DISKING, HARROWING, OR OTHER APPROVED METHODS TO A DEPTH OF APPROXIMATELY 2". TOPSOIL SHALL BE APPLIED ONLY WHEN THE SUBSOIL IS
- IN A LOOSE, FRIABLE CONDITION. D. THE CONTRACTOR SHALL PROTECT BENCHMARKS, UTILITIES, AND EXISTING TREES, SHRUBS, AND OTHER LANDSCAPE FEATURES DESIGNATED FOR PRESERVATION WITH TEMPORARY FENCING OR BARRICADES
- SATISFACTORY TO THE OWNER. E. SUBSOIL ON SLOPES THAT HAVE BEEN HORIZONTALLY GROOVED IN ACCORDANCE WITH THE DRAWINGS SHALL NOT BE LOOSENED.
- F. THE LOOSE DEPTH OF THE CLASS OF TOPSOIL SHALL BE NO LESS THAN 4" (NOT LESS THAN 6" IN MEDIANS: AND SHALL BE SUFFICIENT TO ALLOW THE AREA TO CONFORM TO THE ELEVATIONS SHOWN ON THE DRAWINGS AFTER TOPSOIL SETTLES. IN NO CASE SHALL THE CONSOLIDATED FINISH ELEVATION OF TOPSOIL EXCEED THE ELEVATION OF ADJACENT STRUCTURES. CONSOLIDATED ELEVATION SHALL BE FLUSH WITH THE ADJACENT STRUCTURES.
- G. AFTER TOPSOIL HAS BEEN APPLIED, LARGE CLODS, HARD LUMPS, AND STONES MORE THAN 1" IN THE GREATEST DIMENSION, BRUSH, ROOTS, STUMPS, LITTER, AND FOREIGN MATERIAL SHALL BE REMOVED FROM THE AREA. WHEN THE OPERATION IS COMPLETE, THE AREA SHALL BE IN A CONDITION TO RECEIVE SEED, SOD, OR PLANTS WITHOUT FURTHER SOIL PREPARATION. AREAS SHALL BE STABILIZED WITHIN 15 DAYS AFTER TOPSOIL IS APPLIED.
- H. THE CONTRACTOR SHALL BE REQUIRED TO BACKFILL ALONG EDGES OF CURBS, SIDEWALKS AND ENTRANCES WHERE SETTLEMENT HAS OCCURRED AND RESHAPE AND RESLOPE, WHERE DIRECTED, PRIOR TO PLACEMENT OF TOPSOIL AS WELL AS TO ADD ADDITIONAL TOPSOIL AS REQUIRED DUE TO SETTLEMENT OR EROSION AT NO ADDITIONAL COST TO THE OWNER.

SEEDING / STABILIZATION SPECIFICATIONS

- TOPSOIL STOCKPILE PROTECTION
- APPLY GROUND LIMESTONE AT A RATE OF 90LBS. PER 1000 SQ.FT. APPLY FERTILIZER (10-20-10) AT A RATE 11LBS. PER 1000 SQ.FT.
- ACRE.
- D. MULCH STOCKPILE WITH STRAW OR HAY AT A RATE OF 138 LBS. PER 1000 SQ.FT. E. PROPERLY ENTRENCH A SILT FENCE AT THE BOTTOM OF THE STOCKPILE.
- 18. TEMPORARY STABILIZATION SPECIFICATIONS
- A. APPLY GROUND LIMESTONE AT A RATE OF 184 LBS. PER 1000 SQ.FT. B. APPLY FERTILIZER (10-20-10) AT A RATE 11 LBS. PER 1000 SQ.FT.
- ACRE. D. MULCH STOCKPILE WITH STRAW OR HAY AT A RATE OF 138 LBS. PER 1000 SQ.FT. E. APPLY A LIQUID MULCH BINDER OR TACK TO STRAW OR HAY MULCH.
- 19. PERMANENT STABILIZATION SPECIFICATIONS
- A. APPLY TOPSOIL TO A DEPTH OF 5 INCHES (UNSETTLED) B. APPLY GROUND LIMESTONE AT A RATE OF 184 LBS. PER 1000 SQ.FT. AND WORK FOUR INCHES INTO SOIL.
- C. APPLY FERTILIZER (10-20-10) AT A RATE 11 LBS. PER 1000 SQ.FT. D. APPLY HARD FESCUE SEED AT 20 LBS. PER 1 ACRE. AND CREEPING RED FESCUE SEED AT 20 LBS. PER 1 ACRE. AND PERENNIAL RYEGRASS SEED AT 20 LBS. PER 1 ACRE. AND TALL FESCUE SEED AT
- 20 LBS. PER 1 ACRE. E. MULCH STOCKPILE WITH STRAW OR HAY AT A RATE OF 138 LBS. PER 1000 SQ.FT. F. APPLY A LIQUID MULCH BINDER OR TACK TO STRAW OR HAY MULCH.

HAY BALE AND PLASTIC WASHOUT PIT

HAY BALE AND PLASTIC WASHOUT PIT TO BE BUILT ABOVE GRADE. THE PLASTIC LINING SHOULD BE MINIMUM 10 MIL THICKNESS, FREE OF TEARS OR HOLES THAT WOULD ALLOW THE WASHWATER TO ESCAPE, AFTER THE PIT IS USED TO WASH DOWN THE CHUTES OF MULTIPLE READY MIXED TRUCKS AND THE WASHWATER HAS EVAPORATED OR HAS BEEN VACUUMED OFF. THE REMAINING HARDENED SOLIDS CAN BE BROKEN UP AND REMOVED FROM THE PIT. THIS PROCESS MAY DAMAGE THE HAY BALES AND PLASTIC LINING, IF DAMAGE OCCURS. THE PIT WILL NEED TO BE REPAIRED AND RELINED WITH NEW PLASTIC. WHEN THE HARDENED SOLIDS ARE REMOVED FROM THE PIT. THE WASTE MATERIAL MUST BE RECYCLED OR DISPOSED OF AT AN APPROVE WASTE FACILITY.

TOPSOIL SPECIFICATIONS THE CONTRACTOR SHALL FURNISH ALL LABOR, SUPERVISION, MATERIAL (EXCEPT AS HEREIN PROVIDED),

C. APPLY PERENNIAL RYEGRASS SEED AT 170 LB. PER 1 ACRE. AND ANNUAL RYEGRASS AT 170 LB. PER 1

C. APPLY PERENNIAL RYEGRASS SEED AT 170 LB. PER 1 ACRE. AND ANNUAL RYEGRASS AT 170 LB. PER 1

